

Nombre:
Jose Gabriel Mérida Nájera

Docente:
Arq. Perla Barajas

MATERIA:
Costos y presupuestos

CUATRIMESTRE:
6

FECHA:
15/06/2025

4.368

Lado derecho

$$24 - .30 - 1.40 = 22.30 \text{ m} = 53.52 \text{ m}^2$$

$$2.80 - .40 = 2.40 \text{ m}$$

$$0.22 \times 0.17 = 0.0374$$

$$53.52 \div 0.0374 = 1,431.0160 + 5\% = 1,503 \text{ pas}$$

Lado izquierdo

$$24 - .30 - 1.40 = 22.30 \text{ m} = 53.52 \text{ m}^2$$

$$2.80 - .40 = 2.40 \text{ m}$$

$$0.22 \times 0.17 = 0.0374$$

$$53.52 \div 0.0374 = 1,431.0160 + 5\% = 1,503 \text{ pas}$$

Parte trasera

$$15 - .40 - .80 = 13.80 \text{ m} = 33.12 \text{ m}^2$$

$$2.80 - 0.40 = 2.40 \text{ m}$$

$$0.22 \times 0.17 = 0.0374$$

$$33.12 \div 0.0374 = 885.5614 + 5\% = 930 \text{ pas}$$

Parte frontal

$$7 - .60 = 6.40 \text{ m} = 15.36 \text{ m}^2$$

$$2.80 - .40 = 2.40$$

$$15.36 \div 0.0374 = 410.6951 + 5\% = 432 \text{ pas}$$